


---



# **Smart Construction Retrofit v1.7.1 Update details**

---



EARTHBRAIN

## In addition to conventional RTCM, CMR/CMR+ can now be received.

- Contains fixes for controller FW v1.5.8 and earlier.
- For information on how to update the controller FW, please refer to the article on the support website.  
([Europe](#) / [US](#) / [Australia](#) / [Asia](#))

### ■ Important matter

- To use CMR/CMR+, the **Pilot tablet app must be updated to v1.0.04 or higher.**

### ■ CMR/CMR+ base stations verified to work

#### 【Trimble】

- R750
- BD990/992
- BX940
- SPS855/985
- TVN\_NEAREST\_CMR\_PLUS  
(Ntrip)
- 20\_TVN\_NEAREST\_CMR\_PLUS  
(Ntrip)

#### 【Topcon】

- GB-3
- Hyper VR
- NRST-CMR/NRST-CMR-P  
(Ntrip)

#### 【Hemisphere】

- S321 +

#### 【Hexagon】

- TMBL\_NB  
(Ntrip, CMR+ only)

### ■ Notes

- When using Ntrip services, the RTCM setting is recommended.  
(Due to the large number of satellite types).
  - When changing the type of base station or correction information, reboot the controller after changing the settings.
  - CMR for Leica base stations is not supported.
  - CMRx is not supported.

## How to use

If using CMR/CMR+, change the GNSS settings in the Pilot tablet app (v1.0.04 or higher).  
If reception is not possible, try a controller reboot or Soft / Hard Reset.

